
Waterproofing test








Compression indentation test

Outline of external water pressure test



Testing method

This paper holds the main pipe and the attaching pipe by the SANTAC BRANCH pipe, and holds it for 3 minutes by adding the external water pressure of 0. 1MPa from the outside surface of the pipe and the branch in the state in which the main pipe is fixed, and confirms the existence of the leak of the SANTAC BRANCH by visually. In addition, with the attaching pipe tilted by 20 degrees, 0. 1MPa of external water pressure was added and kept for 3 minutes, and the existence of water leak in the SANTAC BRANCH was confirmed visually. Next, a 5% slippage variant was given to this pipe under the condition of 0 degrees or 20 degrees of inflection angle of the fitting pipe, and O. 1MPa of external water pressure was added to hold for 3 minutes, and the presence of leaks in the SANTAC BRANCH pipe was confirmed visually.

Test Results

Test Results

Types used	Main pipe deflection ratio(%)	External water pressure(MPa)	Bending angle of the mounting tube	External water pressure result	Results	
SANTAC BRANCH number MH-SJ200/150	0	0.1	O°	3 minutes	No abnormal	
		0.1	20°	3 minutes	No abnormal	
	5	0.1	O°	3 minutes	No abnormal	
		0.1	20°	3 minutes	No abnormal	

The specifications and appearance are subject to change without notice for product improvement.



https://www.hrc.co.jp/

Head Office 5351 Minamioka, Minoshima-cho, Fukuyama City, Hiroshima Prefecture Overseas Dept. 1-16-10, Saga, Koto-ku, Tokyo

Water stop flexible joint for fitting pipe junction of sewer pipe SANTAC BRANCH






Innovations Leading the 21st Century-Sealing and Joints Water stop flexible joint for fitting pipe junction of sewer pipe

SANTAC BRA




This product was certified and certified by the Sewerage New Technology Promotion Organization in the Construction Technology Certification Project established by the Construction Technology Certification Council based on the Principal Terms for Implementation of Construction Technology Certification Project (Sewerage Technology) with the aim of contributing to the promotion of the utilization of new construction technology developed voluntarily by the private sector.


Certification No. 1643



Specifications and composition



Comparison of Features and Conventional I




boring portion.

Tighten up to approx. 20

mm.





Insert the mounting tube (Installation angle is within 15°)

8 Peel protective film

Pipe size		Dimensions(mm)						
lain pipe × mounting tube	Product Number	Rd	а	b	С	е	f	
150×100	MH-SJ150/100	82.5	118	98.4	233	200	175	
150×125	MH-SJ150/125	82.5	144	103.5	259	236	175	
200×100	MH-SJ200/100	108.0	118	98.4	233	203	221	
200×125	MH-SJ200/125	108.0	144	98.4	259	218	225	
200×150	MH-SJ200/150	108.0	169	98.4	284	218	225	
250×100	MH-SJ250/100	108.0	118	98.4	233	203	221	
250×150	MH-SJ250/150	133.5	169	98.4	284	237	274	
300×100	MH-SJ300/100	159.0	118	98.4	253	230	314	
300×150	MH-SJ300/150	159.0	169	103.4	304	265	325	
350×100	MH-SJ350/100	159.0	169	98.4	253	230	314	
350×150	MH-SJ350/150	159.0	169	103.4	304	265	325	
400×150	MH-SJ400/150	159.0	169	103.4	304	265	325	
200×150	MH-SJH200/150	133.5	169	98.4	284	237	274	
250×150	MH-SJH250/150	159.0	169	103.4	304	265	325	
300×150	MH-SJH300/150	159.0	169	103.4	304	265	325	
350×150	MH-SJH350/150	159.0	169	103.4	304	265	325	
200×100	MH-SJT200/100	108.0	118	98.4	233	203	221	
200×150	MH-SJT200/150	108.0	169	97.9	284	218	225	
150×100	MH-SJS150/100	82.5	118	97.5	233	200	175	
200×100	MH-SJS200/100	108.0	118	98.4	233	203	221	
200×150	MH-SJS200/150	108.0	169	97.9	284	218	225	
250×100	MH-SJS250/100	108.0	118	98.4	284	233	221	
250×150	MH-SJS250/150	133.5	169	98.4	284	237	274	

stripped and squeezed



④ Place the presser foot cover

(9) Tightening band

(Torque Tighten with

4.9N ·m or more.)

(5) Stop the U-band.



10 Filling back.

* Precautions / Use protective equipment (gloves, etc.) to ensure safety.